



General Engineering Contractor
License No. 754676

ALL QUALIFIED AND/OR CERTIFIED **SBE & DBE** Subcontractors, Truckers and Material/Equipment Suppliers are requested to forward bids/quotes for the following Project. This also includes requests for **SAN FRANCISCO LBE (no formal requests for %'s on this project)** and Non-LBE sub/material quotes from qualified subcontractors, trucking firms and material suppliers for the

L Taraval Improvement Project
SF Zoo to Sunset Boulevard

Contract No. 1306 – ADDENDUM 4- BID DATE CHANGE TO January 10, 2019

The project is also subject to have all subcontractors listed in the bid with a DIR Number. The work under this contract is to construct capital improvements along the L Taraval corridor between SF Zoo and Sunset Boulevard. Work generally consists of the demo, replace paved embedded tie and ballast tracks, single crossover on Taraval & 47th, cobble stone, track pavement and track concrete pavement, OCS, renovate & reconstruct roadway pavement, parking strips, gutters and curbs, platforms, bus shelters, bulb-outs, landscaping, streetlighting, traction power feeder cables & new trolley poles, traffic signals, sewer, fire hydrants. See specifications and drawings as this is a general summary of the work.

Mitchell Engineering request sub proposals in the format of the bid form for the following trades:

- | | |
|--|---|
| -Trucking/Hauling | -Saw Cutting |
| -SWPPP | -Survey |
| -Traffic Control | -Welding |
| -Asphalt Concrete Planning | -Electrical |
| -Concrete Catch Basins | -Street Lighting & Traffic Signals inc. Spare Street Lights |
| -Rail Procurement | -Ductbank Manholes & Utility Boxes |
| -Valves & Fittings | -Overhead Contact System |
| -Misc. Metal | -Handrails & Barrier Railings |
| -Signs inc. infrared signs & ADA | -Landscape including Street Trees, Palm Trees & Shrubs |
| -Trolley Poles | -4" 6" 8" Ductile Iron Tyton Joint Pipe |
| -High Performance Coatings Sub | -Railings & Barrier Railings |
| -Paving including Asphalt Concrete | -Hydrant & Watermain Valve Box |
| -Metal Fabrication | -18" 27" 30" 33" VCP Sewer & 10" VCP Culvert |
| -18" 24" RCP Class V Sewer | -Misc Metals |
| -Concrete including Curb/Gutter, including Boarding Island | |

Insurance/Bonding Questions available through:

City's surety bond program, which assists LBE/SBE or DBE contractors in obtaining bonding and financing for contracts awarded by the City of San Francisco. For further information regarding enrollment eligibility and program services contact Jennifer Elmore at (415) 217-6578. OR Merriwether & Williams Ins Services email bond@imwis.com; call 415/986-3999. Also available Gallagher Construction Services.

-For Bonding Contact: Maureen O'Connell at +1 (415) 391-1500

-For Insurance Contact: Dick Bass at +1(415) 391-1500

Bid Date is January 10, 2019 at 3:00 p.m.

IN ORDER FOR PROPOSALS TO BE CONSIDERED

THEY MUST BE RECEIVED NO LATER THAN January 10, 2019 by 1:00 p.m. in Mitchell Estimating

Please respond with an email with your intent to bid the project. We welcome all questions.

Don Hart - dhart@mitchell-engineering.com or Kathy - kstreblow@mitchell-engineering.com

415-227-1040 – Main Number

415-589-7308 - Direct

415-227-1049 Fax

415/227-1046 Fax

**Mitchell Engineering is a San Francisco Contractor and an Equal Opportunity Employer
We comply with San Francisco Fair Chance Ordinance.**

**Continued Request for
SBE & DBE Subcontractors
L Taraval Improvement Project
SF Zoo to Sunset Boulevard
Contract No 1306**

The Work, as advertised in the City & County of San Francisco Municipal Transportation Agency "Invitation for Bids" and as detailed in the Plans and Specifications, consists generally of the following and Mitchell Engineering welcomes all bidders:

1. Perform selective demolition of existing facilities.
2. Replace existing curved and tangent paved embedded tie and ballast tracks along the L Taraval Line from La Playa and Taraval Streets to Sunset Boulevard with new direct fixation track and fastening systems.
3. Replace one single crossover on Taraval and 47th Avenue with new direct fixation support system.
4. Restore existing cobble stone adjacent to the portion of track to be replaced between 46th and 48th Avenues.
5. Replace existing track pavement with track concrete pavement within the track right-of-way.
6. Replace Overhead Contact System (OCS) special work, trolley wire, tangent spans, feeder spans, and trolley poles for the L Taraval Line west of Sunset Boulevard.
7. Renovate and reconstruct roadway pavement, parking strips, gutters and curb returns.
8. Renovate existing and construct new boarding islands and high level accessible platforms.
9. Coordinate installation of bus shelters with Next Bus signage.
10. Construct bulb-outs and curb ramps to enhance pedestrian safety and comply with current ADA standards.
11. Protect and prune existing trees and provide landscape planting at boarding islands.
12. Provide trash receptacles and bike racks.
13. Provide roadway lighting by removing and relocating LED luminaires from existing to new combination trolley/streetlight poles and provide some lighting on new streetlight poles.
14. Install new streetlight conduit and pull box system.
15. Provide new 120/240 VAC underground and overhead service connections for new streetlights.
16. Provide new traction power feeder cables and grounding for new trolley poles.
17. Install rapid rectangular flashing beacons.
18. Install traffic signal conduit and pull box system for future signalization.
19. Relocate existing sewer facilities and construct concrete manholes along the new sewer alignment.
20. Repair, replace, or construct 6-inch or 8-inch side sewers and connect to the newly constructed main sewer.
21. Construct new concrete catch basins with VCP culverts to ensure proper overland flow drainage around the new platforms and bulb-outs.
22. Plug and fill to abandon existing sewer.
23. Install new ductile iron water mains with service piping and rehabilitate portion of existing cast iron pipe using cast-in-place-pipe (CIPP) method.
24. Install steel casings for water mains at Muni track crossings.
25. Replace all low pressure fire hydrants and associated fittings and valves.
26. Provide excavation and excavation support work for SFWD installation activity and for PG&E hot tapping of deactivated gas mains.

The above description of the Work is a general summary only and does not modify the requirements set out in the Specifications, Drawings or other Contract Documents.

Work is located within the City and County of San Francisco. The estimated cost for this construction contract is \$38.4 million.

The following participation goals have been established for this contract:

Small Business Enterprise (SBE): 10%
African-American Disadvantaged Business Enterprise (DBE): 5%
Woman-Owned Disadvantaged Business Enterprise (DBE): 5%

The project plans and specifications may be viewed in our office at 501 Cesar Chavez St., Ste. 115, San Francisco, CA 94124 or may be obtained from the SFMTA, One South Van Ness Ave., 3rd Flr., San Francisco, CA 94103, Contact is: **Hyun, Evan** Evan.Hyun@sfmta.com